

# LaGrange Street Improvement

Contact: Michael Klahr, City Engineer

[mklahr@cityofnewnan.org](mailto:mklahr@cityofnewnan.org)

770.254.2354 ext. 225

## PROJECT OVERVIEW

---

This project is the full depth reclamation and paving of approximately 5200 lineal feet, centerline, (18,489 square yards) on LaGrange Street from the RR overhead bridge to Newnan High School. Road work is to be substantially complete on or before August 6, 2015. Concrete work includes certain segments of existing sidewalk, driveway aprons, curb/gutter, and curb ramps.

The full depth portion will be re-grading the reclaimed base, between concrete curbs, to a standard crown of 2%, sloping to either side, as a typical section to accommodate a new asphalt pavement section as follows: 8" depth reclaimed base, 2" binder, 1.5" topping. The reclaimed base and binder will match the existing gutter and topping will be placed to face the curb.

Thermoplastic traffic strip and pavement markings, raised reflective pavement markers, including double yellow centerline, white edge line, stop bars, and GDOT standard, ladder type crosswalks.

All sidewalk and curb ramp construction will be in compliance with current ADA standards and constructed to Georgia Department of Transportation standards.

Concrete sidewalk section will be 5' wide and 4" thick; curb/gutter will be 24" type. Driveways will be constructed to 6" thick and will have a 2% transverse slope or match adjacent concrete sidewalk. Detachable warning surfaces will be yellow and set flush with the finished concrete surface at each curb ramp.

This project includes bridge enhancement of the existing bridge over the Norfolk Southern RR and may include decorative street lighting, coating the existing guardrail and adding reflectors, and installing brick banding in the sidewalk area of the bridge.

There may possibly be some utility work.

All structures and plant materials that fall outside of the right-of-way limits will not be disturbed. Grass areas within the right-of-way that is disturbed will be replaced with sod.

This work is to be completed prior to the start of classes for the 2015-2016 school year.